



“कला, संस्कृतियुक्त, स्वच्छ, समुन्नत टोखा नगर”

टोखा नगरपालिका

द्वारा नगरीयपालिका

नगर कार्यपालिकाको कार्यालय



पत्र संख्या :- ०८०/८१
चलानी नं:- २४९०

नगर कार्यपालिकाको कार्यालय
मैजुहिटी, काठमाडौं
बागमती प्रदेश, नेपाल
२०७३

मैजुहिटी, काठमाडौं
बागमती प्रदेश, नेपाल

मिति - २०८०/०९/१८

बिषय — दररेट पेश गर्ने सम्बन्धमा ।

श्री निर्माण व्यावसायीहरु

तेह्रौं नगरसभाको सि.नं. ४९८ मा वडा नं. ३ स्थित मसानकाली मन्दिर पुनः निर्माणको लागि विद्यमान जिर्ण मन्दिर भत्काउने कार्य शिर्षकको आयोजना स्वीकृत भई मिति २०८०/८/२८ को नगरकार्यपालिका बैठकबाट उल्लेखित मन्दिरको विद्यमान संरचना भत्काउने सम्बन्धमा गरेको निर्णयानुसार तयार भएको संलग्न BOQ अनुसारको दररेट तपशिलको मिति, समय र स्थानमा तपशिलका कागजातहरु सहित खामबन्दी प्रस्ताव पेश गर्नु हुन अनुरोध छ ।

प्रस्ताव साथ संलग्न गर्नु पर्ने कागजातहरु:

१. सम्बन्धित फर्म/ कम्पनिको निवेदन
२. कम्पनि / फर्म दर्ता नविकरण प्रमाणपत्रको प्रतिलिपी
३. आ.ब.२०८०/८१ को लागि नविकरण भएको निर्माण व्यावसायी ईजाजतपत्र
४. भ्याट दर्ता प्रमाणपत्र
५. आ.ब.२०७९/८० को करचुक्ता प्रमाणपत्र वा म्याद थप वा आय विवरण पेश गरेको निस्सा
६. कार्यालयबाट जारी संलग्न BOQ मा फर्मको छाप र आधिकारीक व्यक्तिको दस्तखत हुनुपर्ने ।

खामबन्दी प्रस्ताव पेश गर्नु पर्ने अन्तिम मिति,समय र स्थान		प्रस्ताव खोलिने मिति, समय र स्थान	
मिति	२०८०/०९/२४ गते	मिति	२०८०/०९/२४
समय	मध्यान्ह १२:०० वजे भित्र	समय	दिनको १:०० वजे
स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं	स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं

पूनन्ध: छनौट भई सम्झौता गर्न नआएमा कालो सूचिमा राखिने प्रकृया अगाडि बढाईनेछ । अन्य कुरा सावर्जनिक खरिद ऐन तथा नियमावली वमोजिम हुनेछ ।

२०८०/०९/१८
(अनिल प्रसाद जोशी)
अधिकृत सातौं



Tokha Municipality
Office of Municipal Executive
Maljuhtu, Kathmandu
Province no. 3, Nepal
Bill Of Quantities



नेपाल
समाजवादी गणतन्त्र
राज्यको काठमाडौं
शान्ति पर्यटन क्षेत्र

आर्थिक वर्ष: २०७८

कार्यालय वा परियोजनाको नाम: मसानकाली मन्दिर पुन निर्माणको लागि विद्यमान निर्माण अन्तर्गत कार्य
कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल: टोखा नगरपालिका - ३
सम्पन्न हुने अनुमानित अवधि:

S.N	Description of works	Unit	Quantity	Contractor's Unit Rate (Rs.)		Amount	Remarks
				In Figure	In words		
1.00	M.S. black pipe truss with IS or BS section including jointing, fixing, erection & colouring with all necessary MS bed plate & shoe angles anchor bolts leas sheeling or cement grouting as per drawing & instuction all complete.	Kg	960.53				
2.00	Supplying and Fitting 0.5mm thick coloured sheet 150mm width making gutter including fixing in proper shape & size with all necessary trails screws bolts & nuts Washer J & L hooks etc as per drawing & instruction all complete.	Sqm	139.80				
3.00	Providing, fabricating & fixing iron gate using 50mm dia. medium black pipe frame with 25mm dia. Medium black pipe sub gate frame, 25x25x 2mm thick square pipe, 16 gauge MS sheet, 20x4.5 mm grill plate on top of gate and other necessary hinges, tower bolt, aldrops and plates with one coat of metal primer & enamel paint as per design drawing, specifications and instructions of site engineer all complete	Sqm	9.51				
4.00	18mm ply board	sqm	6.39				
5.00	SCAFFOLDING WORK	Sqm	64.00				

Handwritten signature and date 2078/15/19C

Handwritten signature and date 2078/15/19C

Handwritten signature and date 2078/15/19C

S.N	Description of works	Unit	Quantity	Contractor's Unit Rate (Rs.)		Amount	Remarks
				In Figure	In words		
6.00	Dismantling of c/m or lime, surkhi molar wall of existing Building and other structure at site, proper stacking of reusable material like wood and metals and disposal of non-usable debris at hauling of up to 10m from the site etc all complete.	Cum	24.28				
7.00	Dismantling & removing RCC or RBC of existing Building and other structure at site, proper stacking of reusable material like wood and metals and disposal of non-usable debris at hauling of up to 10m from the site etc all complete.	Cum	27.68				
8.00	Providing, fabricating & fixing collapsible iron gate and other necessary hinges, tower bolt, aldrops and plates with one coat of metal primer & enamel paint as per design drawing, specifications and instructions of site engineer all complete	sqm	4.88				
9.00	INFORMATION BOARD	LS	1.00				
	Sub Total (B)						
	Total (A+B)						
	13 % VAT						
	Total Amount with VAT						
	4% Contingency						
	Total Amount with Vat and Contingency						

[Signature]
202015196

[Signature]
202015196

[Signature]