




“कला संस्कृतियुक्त, स्वच्छ समुन्नत टोखा नगर”

टोखा नगरपालिका
द्वारा नगरपालिका

नगर कार्यपालिकाको कार्यालय

पत्र संख्या: ०८२/८३ (योजना तथा अनुगमन शाखा)

च.नं.: ९०२



मैजुहिटी, काठमाडौं
बागमती प्रदेश, नेपाल।

मिति: २०८२/०६/०९

ने.सं.: ११४५ कौलाथ्व ४ बिहीबार

श्री सम्बन्धित व्यावसायीहरू

बिषय — दररेट पेश गर्ने सम्बन्धमा ।

१७ औं नगरसभाको सि.नं. ११३८ मा वडा नं. १० स्थित सडकहरूमा सिस्किवामेरा जडान कार्यको लागि विनियोजित बजेटको कार्यक्रम कार्यान्वयनको लागि तयार भएको संलग्न BOQ अनुसारको सामग्रीहरूको दररेट उल्लेख गरी तपशिलको मिति, समय र स्थानमा तपशिलका कागजातहरू सहित प्रस्ताव पेश गर्नु हुन अनुरोध छ ।

प्रस्ताव साथ संलग्न गर्नु पर्ने कागजातहरू:

१. सम्बन्धित फर्म/ कम्पनिको निवेदन
२. कम्पनि / फर्म दर्ता नविकरण प्रमाणपत्रको प्रतिलिपी
३. भ्याट दर्ता प्रमाणपत्र
४. आ.ब.२०८०/८१ को करचुक्ता प्रमाणपत्र
५. कार्यालयबाट जारी संलग्न BOQ मा फर्मको छाप र आधिकारीक व्यक्तिको दस्तखत हुनुपर्ने ।
६. संलग्न Technical Specifications fully comply गरी सहिछाप गरेको हुनु पर्ने ।
७. कम्तिमा १ बर्ष वारेन्टी समय भएको पत्र संलग्न हुनुपर्नेछ ।


खामबन्दी प्रस्ताव पेश गर्नु पर्ने अन्तिम मिति,समय र स्थान		प्रस्ताव खोल्ने मिति, समय र स्थान	
मिति	२०८२/६/१२ गते	मिति	२०८२/६/१२
समय	मध्यान्ह १२:०० वजे भित्र	समय	दिनको १:०० वजे
स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं	स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं

पूनश्च: छनौट भई सम्झौता गर्न नआएमा कालो सूचिमा राखिने प्रकृया अगाडि बढाईनेछ । अन्य कुरा सोबर्जिनिक खरिद ऐन तथा नियमावली बमोजिम हुनेछ ।

(Signature)
८२६१९

अनिल प्रसाद जोशी
बरिष्ठ शाखा अधिकृत





स्थानीय तह
दोखा नगरकार्यपालिकाको कार्यालय
कार्यालय कोड नं.:
BILL OF QUANTITY (BOQ)

Signature

Signature

Signature

कार्यालय वा परियोजनाको नाम: दोखा नगरपालिका (पूर्वाधार विकास / सुरक्षा) वडा नं १०
कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल: सिमिक्यामेरा जडान

बजेट रु.:
१०,००,०००.००
बजेट उपशिर्षक नं. ११३८

S.No.	Description	Qty	Unit	Rate		Total
				In Figures	In Words	
A.	Provisional work					
1.00	Provide and installation of project information Board as specified per instruction.	1.00	Ps			
B.	Construction works					
1.00	Supplying, installing and testing 4MP ColorVu Fixed Bullet Network CameraMax 2560 x 1440 @25fps, 4 mm/6 mm fixed lens, H.265+, H.264+, 120dB WDR, 0.0014 @ F1.0 (1/30 s. AGC ON), 0.002 @ F1.2 (1/30 s. AGC ON), 0 Lux with LED on 12 VDC & PoE (802.3af, class 3), Built-in micro SD/SDHC/SDXC slot, up to 128G, 1P67, BLC/D DNR/HLC/Audio -24-hour colourful video.	14.00	Nos.			
2.00	10 TB HDD Supplying, installing and testing 10TB Internal Hard Disk, 10TB Storage Capacity, 3.5" Form Factor, 12 Gb/s SAS Interface, 256MB Cache, 7200 rpm, Up to 245 MB/s Sustained Data Transfers, 2,500,000 Hours MTBF, 8760 Power-On Hours per Year.	1.00	Nos.			
3.00	64 Channel NVR: 64 Channel NVR, 64ch 8-SATA Ultra 265/H.265/H.264 NVR, Support Ultra 265/H.265/H.264 NVR, 64-channel input, Third-party IP cameras supported with ONVIF conformance: Profile S, Profile G, Profile T, Support 1-ch HDMI, 1-ch VGA, HDMI and VGA simultaneous output, Up to 8MP resolution recording, 8 SATA HDD up to 10TB, hdd monitoring	1.00	Nos.			
4.00	16 Port Gigabit Network Switch: Supplying, installing and testing Networking Switch 10/100/1000 Mbps	1.00	Nos.			

Sanjay Singh Chauhan

S.No.	Description	Qty	Unit	Rate		Total
				In Figures	In Words	
5.00	5 Port Gigabit Network Switch: Supplying, installing and testing Networking Switch 10/100/1000 Mbps.	14.00	Nos.			
6.00	Media converter: Supplying, installing and testing Media converter 10/100 Mbps.	14.00	Nos.			
7.00	Optical fiber 6 core.	525.00	Rm			
8.00	Power cable: 0-1 cable for power.	525.00	Rm			
9.00	Optical Patch cord: Optical Patch cord 5m.	14.00	Unit			
10.00	Splicing charge: Optical fibre splicing charge.	42.00	Unit			
11.00	Supplying and installing Tiffin Enclosure all complete.	14.00	Nos.			
12.00	Supplying and installing Metal Box all complete.	14.00	Nos.			
13.00	Power Adapter: Power adapter 12v, 2Amp.	14.00	Nos.			
14.00	Cat6 Cable: 1 drum Pure copper.	1.00	Nos.			
15.00	Accessories: Cable tie, Tape, RJ-45 etc including all installation materials.	1.00	Ls.			
Sub Total without VAT and P.S.						
VAT 13%						
Total with VAT and P.S.						

Name Of Firm :-
 Proprietor's Name :-
 Address of Proprietor:-